BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18388/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Excavation of Temporary Immersion Tank for Lord Ganesh Idols at Doddabommasandra Lake in Ward No. 10, (Doddabommasandra), Vidyaranyapura Sub Division. (For 2016-17 year)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R S THYAGARAJ		
				In Figures		In Words
1	42	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	Cum	156.88	6588.96	Rupees One Hundred Fifty Six and Eighty Eight Paise Only
2	214.5	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	188.68	40471.86	Rupees One Hundred Eighty Eight and Sixty Eight Paise Only
3	214.5	Above 1.5 Mtrs Depth Add 25% Extra	Cum	235.86	50591.97	Rupees Two Hundred
4	820	Code 0516 - Providing Plastic Sheet etc complete as per specifications and directions of engineer in charge of the work	Sqm	6.0	4920.00	Rupees Six Only
5	165	Supply of water Through water Tank for filling Tank etc complete as per specifications and directions of engineer in charge of the work	Each	360.0	59400.00	Rupees Three Hundred Sixty Only
6	12.5	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal Component etc complete as per specifications and directions of engineer in charge of the work	Cum	750.0	9375.00	Rupees Seven Hundred Fifty Only
7	66	Hire charge of pumping water 3.5 KL/hr capacity Pump etc complete as per specifications and directions of engineer in charge of the work	Hr	50.0	3300.00	Rupees Fifty Only
8	165	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the pooja Time etc complete as per specifications and directions of engineer in charge of the work	Days	244.54	40349.10	Rupees Two Hundred Forty Four and Fifty Four Paise Only
9	480	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge	Mtrs	65.0	31200.00	Rupees Sixty Five Only
10	13200	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc complete as per specifications and directions of engineer in charge of the work	Sft	8.0	105600.00	Rupees Eight Only
11	165	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc complete as per specifications and directions of engineer in charge of the work	Rft	17.0	2805.00	Rupees Seventeen Only
12	220	Hire Charge for Armless Plastic Chairs etc complete as per specifications and directions of engineer in charge of the work	Nos	4.0	880.00	Rupees Four Only
13	110	Hire Charge for Wooden Table of Size 6ft x 2ft etc complete as per specifications and directions of engineer in charge of the work	Nos	40.0	4400.00	Rupees Forty Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R S THYAGARAJ		
				In Figures		In Words
14	1100	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathe daluminium wire etc complete as per specifications and directions of engineer in charge of the work	Mtrs	9.0	9900.00	Rupees Nine Only
15	66	Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges etc complete as per specifications and directions of engineer in charge of the work	Hr	562.0	37092.00	Rupees Five Hundred Sixty Two Only
16	88	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time etc complete as per specifications and directions of engineer in charge of the work	Nos	285.0	25080.00	Rupees Two Hundred Eighty Five Only
17	10	Hire charges compoment name 1087 Crane charges etc complete as per specifications and directions of engineer in charge of the work	Day	4000.0	40000.00	Rupees Four Thousand Only
18	357.5	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour etc complete as per specifications and directions of engineer in charge of the work	Cum	77.76	27799.20	Rupees Seventy Seven and Seventy Six Paise Only
		Total			499753.09	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

31/8/16